

LANE COMMUNITY COLLEGE LONGHOUSE PROJECT



IN-KIND MATERIALS LIST

1. SITE WORK

- Crushed rock (3/4") 550 cu. yd.
- 50-100# basalt 10 cu. yd.
- 3'-4' basalt boulders 20 pieces
- Pavers 1700 SF

2. CONCRETE

- 130 cu. yd.

3. RE-BAR

- #4 & #5 4 ton

4. WOOD: CEDAR

- Ship-lap (1 x 6) clear or tight-knot 1,800 sf coverage
- Cedar shingles (8" exp.) 5,500 sf coverage

5. WOOD: STRUCTURAL

- 8 x 8 Fir 70 lin. ft.
- 6 x 12 Fir 150 lin. ft.
- 4 x 8 Fir 2,200 lin. ft.
- 2 x 8 Fir 600 lin. ft.
- 2 x 6 Framing Studs (Roof) 6,000 sf
- 2 x 6 Ceiling Joists 1,700 lin. ft.
- 2 x 6 T & G Hemlock Decking (Roof) 2,500 sf
- 3x6 Lam. Decking 1,000 sf
- CDX Plywood 5,000 sf
- 2x6 Studs & Sheathing (Ext. Walls) 6,000 sf

6. WOOD: LOGS

Cedar Logs (Exterior Non-Bearing):

- 12"Ø 4@8'
- 12"Ø 2@12'
- 16"Ø 2@10'
- 16"Ø 1@32'

Doug Fir/Larch (Interior Bearing):

- 10"Ø 4@5'
- 12"Ø 6@9'
- 12"Ø 4@30'
- 16"Ø 6@8'
- 16"Ø 8@10'
- 16"Ø 2@26'
- 16"Ø 4@30'
- 20"Ø 16@12'
- 24"Ø 6@36'

7. WOOD: TRUSSES

- Engineered Trusses/4:12 pitch, 56' span Max. 14 trusses
- Engineered Eave Trusses/4:12 pitch, 12' span Max. 46 trusses

8. WOOD: FLOORING

- 3/4" x 4" T & G 1,600 sf

StastnyBrun Architects, Inc.

LANE COMMUNITY COLLEGE LONGHOUSE PROJECT



9. HARDI PANEL SIDING (Alternate):
- 4 X 8 Sheets 5,500 sf coverage

10. METALS (GALVALUME)
- Standing Seam Roofing (2' pans) 6,500 sf coverage
 - Flat Seam Siding 1,000 sf coverage
 - Gutters/Downspouts 250 lin. ft.

11. INSULATION
- 3" Rigid Insulation 5,000 sf
 - 1 1/2" Rigid Insulation 800 sf
 - R-19 Batt Insulation 4,000 sf
 - R-38 Batt Insulation 3,000 sf

12. FINISHES
- 5/8" GWB & WRGWB 20,000 sf
 - Acoustical ceilings 2,000 sf
 - Sheet Vinyl Flooring 400 sf
 - Rubber Base 400 lf
 - FRP Wainscot 400 sf

13. TILE
- Base 300 lin. ft.
 - Walls 750 sf

14. RESTROOMS/DRESSING
- Toilet Partitions 4 reg/2hndcp
 - Fixtures 5 sinks
6 toilets
2 urinals
 - Stainless Steel Counters 16 lin. ft.
 - 1-Piece ADA Shower Unit 2 ea
 - Toilet Accessories 1 ls

15. KITCHEN EQUIPMENT
- 6 Burner Range w/Oven-Commercial Grade 1 ea
 - Refrigerator - Commercial Grade 1 ea
 - Dishwashers - Commercial Grade 2 ea
 - Stainless Steel Countertops 35 lin. ft.
 - Base Cabinets/Shelving 35 lin. ft.
 - Stainless Steel Sink 2 ea
 - Janitor Mop Sink 1 ea

16. FIRE SPRINKLER SYSTEM
- Design, fabricate & install 7,000 sf

Approximate value of In-Kind Materials Listed Above - \$205, 000